Bruhath Bangalore Mahanagara Palike

Office of the Executive Engineer
Electrical Division, Dasarahalli Zone
Bruhath Bengaluru Mahanagara Palike

"DTS for Kind Approval"

Name of the Work:-Providing Electrical Repair and additional Light fittings to Parks at Ward No-12

Sl. No.	Approved Qty	Description	Unit	Approved Rates		Amount
				in Figures	in words	
1	10	Supplying and fixing MV lamps on existing fitting mounted on tubular pole	No	205.00	Rupees Two Hundred and Five Only	2050.00
2	10	Supply and fixing/replacing of choke for Mercury Vapour lamp fitting in existing fitting mounted on tubular pole.	No	506.00	Rupees Five Hundred and Six Only	5060.00
3	3	Supply and fixing of 230 volts Porcelain holder for MV/SV/MH lamp a) 70-150 Watts lamp Holder	No	74.00	Rupees Seventy Four Only	222.00
4	5	Supplying and fixing/replacement of ignitor suitable for 70 to 400 watts SV/MH fittings b) Group B	No	500.00	Rupees Five Hundred Only	2500.00
5	330	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Class I. Class 'A' PVC Cable	Per Mtr	150.00	Rupees One Hundred and Fifty Only	49500.00
6	330	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required. I. In existing trench /duct.	Rmtr	8.00	Rupees Eight Only	2640.00
7	3	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and	Each	1495.00	Rupees One Thousand Four Hundred and Ninety Five Only	4485.00
8	3	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.	Each	3865.00	Rupees Three Thousand Eight Hundred and Sixty Five Only	11595.00
9	15	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 16 sqmm	Each	14.00	Rupees Fourteen Only	210.00
10	2	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and washers etc., Group 'A' PWD SR 2007-08	Each	4200.00	Rupees Four Thousand Two Hundred Only	8400.00
11	500	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or consealed system of wiring.I Group A .c) 2.5 sqmm	Per Mtr	25.00	Rupees Twenty Five Only	12500.00

12	295	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB 1-2, P-7)b. In hard Soil	Rmtr	50.00	Rupees Fifty Only	14750.00
13	6	Supplying and fixing angle iron frame work fabricated out of M.S angle iron… and M.S. flat… with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a) a)	Rmtr	240.00	Rupees Two Hundred and Forty Only	1440.00
14	15000	Fabricating supplying and mounting MS box made out… SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof	sqcm	0.33	Rupees Zero Only Paise Thirty Three Only	4950.00
15	1	Fabricating, supplying and erecting swaged tubular pole of height… Mtr having three sections and providing two coats of re oxide paint and finished with two coats of enameled paint of approved quality and colour and M.S.	Each	13500.00	Rupees Thirteen Thousand Five Hundred Only	13500.00
16	2	Supplying High pressure… Watts Metal halide flood light luminary suitable for use with high pressure metal halide lamp with integrated control gear. The fitting shall be non corrosive high pressure die cast aluminium	Each	8000.00	Rupees Eight Thousand Only	16000.00
					Total Tender Prises Rs	**149802.00**
(Rs One lakh forty nine thousand eight hundred and two Only)						

I am prepared to take up the above work at --------% above/below (In Words ---------- ----------) the rates quoted in the Schedule 'B'

CONTRACTOR

EXECUTIVE ENGINEER (Ele)
DASARAHALLI ZONE, BBMP

"DTS Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ವಿದ್ಯುತ್ ವಲಯ,
ಬಿ.ಬಿ.ಎಂ.ಪಿ